



Maulana Azad National Institute of Technology, Bhopal
(An Institution of National Importance under Ministry of Education, Govt. of India)

No. CM/2026/NIQ/ **4852**

Date: - **11-08-2026**

NOTICE INVITING QUOTATIONS

The item rate based quotation as per Delhi schedule of Rate CPWD, with up to date amendments are invited for the following work from the empanelled contractors of the Institute. The quotations can be dropped in a box (**BOX No. 1**) placed at the Civil Maintenance section office till 18-08-2026 at 4:00 PM. The same will be opened on next working day at 11:00 am at Civil Maintenance section office in presence of committee members:-

S.No.	Name of Work	Estimated Cost (in Rs.)	Completion period
1.	Providing and fixing false ceiling at LRC (Bajaj Lab setup), MANIT Bhopal	4,88,586/-	20 Days

Salient Feature of Works

1. An agreement will be executed before work order.
2. Clauses of General Condition of Contract shall be applied.
3. Rate for each item and amount should be entered along with gross total amount.
4. Other conditions will be same as per Institute norms.
5. Descriptions of Items works are enclosed.
6. Out sourcing / Subletting of work will not be permitted as per rules.
7. Security Deposit of 5% of the bill amount will be retained for a period of 6 months. Any kind of defects occurring during the defect liability period should be repaired by the contractor.

Note: - 1. Authority reserves the right to reject any/all quotation without assigning any reason thereof and can also reduce or enhance the quantity of work.
2. The quotation needs to be submitted on the letter pad of the firm duly sealed and signed on all pages. The envelope containing the quotation should bear/have the details of concerned firm, NIQ No. and name of work.
3. Incomplete quotations will be rejected.

Authority – Approved by competent authority.


11/08/2026
Executive Engineer

Copy to:-

1. Dean (P&D)
 2. Associate Dean (CM)
 3. PIC (Website) **for uploading on Institute website and intimating uploading confirmation to the undersigned.**
 4. PA to Registrar for Kind information of Registrar.
 5. PA to Director for Kind information of Director.
- Contractors (By e-mail/mobile phone).

SCHEDULE OF QUANTITIES

PROVIDING AND FIXING FALSE CEILING AT LRC (BAJAJ LAB SETUP) AT MANIT BHOPAL.

S.NO.	DESCRIPTION OF ITEMS	QTY	UNIT	Rate(Rs.Ps). In Figures	Rate(Rs.Ps). In Figures	Amount (Rs. Ps.)
1	DSR ITEMS NO. 15.57					
	15.57 Dismantling aluminium/ Gypsum partitions, doors, windows, fixed glazing and false ceiling including disposal of unserviceable material and stacking of serviceable material with in 50 meters lead as directed by Engineerin- charge.					
	Total Quantity	100.00	sqm			
2	DSR ITEMS NO. 12.52.2					
	12.52 Providing and fixing tiled false ceiling of specified materials of size 595x595 mm in true horizontal level, suspended on inter locking metal grid of hot dipped galvanized steel sections (galvanized @ 120 grams/ sqm, both side inclusive) consisting of main "T" runner with suitably spaced joints to get required length and of size 24x38 mm made from 0.30 mm thick (minimum) sheet, spaced at 1200 mm center to center and cross "T" of size 24x25 mm made of 0.30 mm thick (minimum) sheet, 1200 mm long spaced between main "T" at 600 mm center to center to form a grid of 1200x600 mm and secondary cross "T" of length 600 mm and size 24x25 mm made of 0.30 mm thick (minimum) sheet to be interlocked at middle of the 1200x600 mm panel to form grids of 600x600 mm and wall angle of size 24x24x0.3 mm and laying false ceiling tiles of approved texture in the grid including, required cutting/making, opening for services like diffusers, grills, light fittings, fixtures, smoke detectors etc. Main "T" runners to be suspended from ceiling using GI slotted cleats of size 27 x 37 x 25 x1.6 mm fixed to ceiling with 12.5 mm dia and 50 mm long dash fasteners, 4 mm GI adjustable rods with galvanised butterfly level clips of size 85 x 30 x 0.8 mm spaced at 1200 mm center to center along main T, bottom exposed width of 24 mm of all T-sections shall be pre-painted with polyester paint, all complete for all heights as per specifications, drawings and as directed by Engineer-in-charge.					
	12.52.2 GI Metal Ceiling Lay in perforated Tegular edge global white color tiles of size 595x595 mm and 0.5 mm thick with 8 mm drop; made of GI sheet having galvanizing of 100 gms/sqm (both sides inclusive) and 20% perforation area with 1.8 mm dia holes and having NRC (Noise Reduction Coefficient) of 0.5, electro statically polyester powder coated of thickness 60 microns (minimum), including factory painted after bending and perforation and backed with a black Glass fiber acoustical fleece.					
	Total Quantity	226.20	sqm			
	Total Amount					
3	Other Misc. work as per on % rate Basis Based on dsr 2023 Rs. 15000/-					
	Total Gross Amount (Rs.Ps.)- In Figures					
	Total Gross Amount (Rs.Ps.)- In word					

Name Seal & Signature of Contractor