



CM/NIQ NO/ 4435

मौलाना आजाद राष्ट्रीय प्रौद्योगिकी संस्थान, भोपाल
(शिक्षा मंत्रालय, भारत सरकार के अधीन राष्ट्रीय महत्त्व का संस्थान)
Maulana Azad National Institute of Technology, Bhopal
(An Institution of National Importance under Ministry of Education, Govt. of India)

Date: 30/06/2026

NOTICE INVITING QUOTATIONS

The item rate based quotation as per Delhi schedule of Rate CPWD, with up to date amendments are invited for the following work from the empanelled contractors of the Institute. The quotations can be dropped in a box (BOX No. 2) placed at the Civil Maintenance section office till 08/07/26 at 2:00 PM. The same will be opened on Same day at 04:00 PM at Civil Maintenance section office in presence of committee members:-

S.N	Name of Work	Estimated Cost (in Rs.)	Completion period
28	Construction of Civil Structure For Handling of Heavy Dies of Injection Moulding Machine in Nechnical Workshop at MANIT Bhopal.	92,90,9/-	20Days

Salient Feature of Works

1. An agreement will be executed before work order.
2. Rate for each items and amount should be entered along with gross total amount.
3. Other conditions will be same as per Institute norms.
4. Descriptions of Items works are enclosed.
5. Out sourcing/Subletting of work will not be permitted as per rules.
6. Security Deposit of 5% of the bill amount will be retained for a period of 06 months. Any kind of defects occurring during the defect liability period should be repaired by the contractor.

Note:

1. Authority reserves the right to reject any/all quotation without assigning any reason thereof and can also reduce or enhance the quantity of work.
2. The quotation needs to be submitted on the letter pad of the firm duly sealed and signed on all pages. The envelope containing the quotation should bear/have the details of concerned firm, NIQ No. and name of work.
3. Incomplete quotations will be rejected.

Authority: Competent Authority Approval No. CM/26/4292 DATED 25/06/2026.


Associate Dean (Civil Maintenance)

Copy to: -

1. Dean (P&D).
2. Registrar for kind information.
3. PA to Director for Kind information of Director.
4. PIC (Website) **for uploading on Institute website and intimating uploading confirmation to the undersigned.**
5. To all empanelled contractors (By e-mail/mobile phone).
6. Display on Notice Board.

**Estimate for Construction of Civil Structure for injection Moulding Machine in
Mechanical Department at MANIT Bhopal**

S.NO.	DESCRIPTION	QTY	UNIT	RATE	AMOUNT
1	DSR 2023 ITEMS NO.15.25				
	15.25 Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.				
	Total Quantity	4.5	sqm		
2	DSR 2023 ITEMS NO.15.2.1				
	15.2 Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer -in-charge.				
	15.2.1 Nominal concrete 1:3:6 or richer mix (including equivalent design mix)				
	Total Quantity	0.675	cum		
3	DSR 2023 ITEMS NO.2.8.1				
	2.8 Earth work in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m.				
	2.8.1 All kinds of soil				
	Total Quantity	9.45	. Cum		
4	DSR 2023 ITEMS NO.4.1.4				
	4.1 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.4 1:2:4 (1 Cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 40 mm nominal size derived from natural sources)				
	Total Quantity	0.675	cum		
5	DSR 2023 ITEMS NO.5.1.2				
	5.1 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
	5.1.2 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)				
	Total Quantity	1.92	cum		
6	DSR 2023 ITEMS NO.5.9.1				
	5.9 Centering and shuttering including strutting, propping etc. and removal of form for				
	5.9.1 Foundations, footings, bases of columns, etc. for mass concrete				

	Total Quantity	3.2	sqm		
7	DSR 2023 ITEMS NO.5.22.6				
	5.22 Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
	5.22.6 Thermo-Mechanically Treated bars of grade Fe-500D or more.				
	Total Quantity	231.4	kg		
8	DSR 2023 ITEMS NO.10.2				
	10.2 Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.				
	Total Quantity	105.6	kg		
9	NON DSR ITEMS				
	Cutting , hoisting , aligning and erection of existing structural steel members such as hollows section, MS tubes , I-section, Channels, Angles etc. Including gas cutting, grinding, welding with approved electrodes, lifting, fixing in position, scaffolding , T&P and touch-up painting complete as directed by Engineer-in-charge.				
		561.64	kg		
10	Other Misc as per % rate of DSR	5000			

SEAL & SIGN WITH OF CONTRACTOR