

SCHEDULE OF QUANTITIES						
Name of work : Track & Field, Cricket Ground, and Football Ground – Stair Painting Work at MANIT Bhopal						
S. No.	Description	Qty	Unit	Rate (Rs. Ps.)- In Figures	Rate (Rs. Ps.)- In Words	Amount (Rs. Ps.)
1	DSR 20203 ITEM No. 13.91					
	13.91 Removing dry or oil bound distemper, water proofing cement paint and the like by scrapping, sand papering and preparing the surface smooth including necessary repairs to scratches etc. complete.					
	Total Qty	1979.75	Sqm			
2	DSR 20203 ITEM No. 13.52					
	13.52 Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete.					
	13.52.2 On concrete work					
	Total Qty	1979.75	Sqm			
3	DSR 2018 ITEM No.13.99.1					
	13.99 Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : 13.99.1 One or more coats on old work					
	Total Qty	45.00	Sqm			
4	Other Misc. Items on % basis based on DSR 2023 for Rs. 20000/--					
	Total Gross Amount (Rs. Ps.)- In Figures					
	Total Gross Amount (Rs. Ps.)- In words					

Name, Seal & Signature of Contractor