



मौलाना आजाद राष्ट्रीय प्रौद्योगिकी संस्थान, भोपाल
(शिक्षा मंत्रालय, भारत सरकार के अधीन राष्ट्रीय महत्त्व का संस्थान)
Maulana Azad National Institute of Technology, Bhopal
(An Institution of National Importance under Ministry of Education, Govt. of India)

No.CM/2026/NIQ/ 4992

Date: 18-08-2026

NOTICE INVITING QUOTATIONS

The item rate based quotation as per Delhi schedule of Rate CPWD, with up to date amendments are invited for the following work from the empanelled contractors of the Institute. The quotations can be dropped in a box (BOX No. 1) placed at the Civil Maintenance section office till 25-08-2026 at 2:00 PM. The same will be opened on Same day at 04:00 PM at Civil Maintenance section office in presence of committee members:-

S.N	Name of Work	Estimated Cost (in Rs.)	Completion period
	Levelling and flooring of G08 In Mechanical Department At MANIT Bhopal .	1,83,515/-	1 months

Salient Feature of Works

1. An agreement will be executed before work order.
2. Rate for each items and amount should be entered along with gross total amount.
3. Other conditions will be same as per Institute norms.
4. Descriptions of Items works are enclosed.
5. Out sourcing/Subletting of work will not be permitted as per rules.
6. Security Deposit of 5% of the bill amount will be retained for a period of 06 months. Any kind of defects occurring during the defect liability period should be repaired by the contractor.

Note:

1. Authority reserves the right to reject any/all quotation without assigning any reason thereof and can also reduce or enhance the quantity of work.
2. The quotation needs to be submitted on the letter pad of the firm duly sealed and signed on all pages. The envelope containing the quotation should bear/have the details of concerned firm, NIQ No. and name of work.
3. Incomplete quotations will be rejected.
4. The work shall be carried out strictly in accordance with the latest CPWD Specifications, CPWD DSR, General Conditions of Contract (GCC), relevant CPWD Codes/Manuals and all other applicable rules, standards and norms of CPWD.

Authority: Competent Authority Approval No. MANIT/DPS/2740 Date 13/08/2026

Ashish
18/8/2026
Executive Engineer
(Civil Maintenance)

Copy to: -

1. Dean (P&D)
2. Associate Dean (CM)
3. Registrar for kind information.
4. PA to Director for Kind information of Director.
5. PIC (Website) **for uploading on Institute website and intimating uploading.**
6. **confirmation to the undersigned.**
7. To all empanelled contractors (By e-mail/mobile phone).
8. Display on Notice Board.

BOQ for Levelling and Flooring of G-08 In Mechanical Department at MANIT Bhopal

NO.	DESCRIPTION OF ITEMS	QTY	UNIT	RATE	AMOUNT	AMOUNT IN WORDS
1	DSR 2023 ITEMS NO. 15.23.1					
	15.23 Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.15.23.1 For thickness of tiles 10 mm to 25 mm					
	Total Quantity	50	sqm			
2	DSR 2023 ITEMS NO. 4.1.10					
	4.1 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :					
	4.1.10 1:5:10 (1 cement : 5 coarse sand (zone-III) derived from natural sources : 10 graded stone aggregate 40 mm nominal size derived from natural sources) cum					
	For Sub Base Filling					
	Total Quantity	5	cum			
3	DSR 2023 ITEMS NO. 4.1.3					
	4.1 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :					
	4.1.3 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources) cum0					
	For Base					
	Total Quantity	5	cum			
4	DSR 2023 ITEMS NO. 4.1.3					
	11.41 Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20 mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/sqm including grouting the joints with white cement and matching pigments etc., complete.					
	11.41.2 Size of Tile 600x600 mm sqm					
	Total Quantity	50	sqm			
5	DSR 2023 ITEMS NO. 4.1.3					
	6.2 Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in:					

	6.2.1 Cement mortar 1:4 (1 cement : 4 coarse sand) cum					
	For Base Boundary					
	Total Quantity	0.75	cum			
6	DSR 2023 ITEMS NO. 4.1.3					
	13.82 Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.					
	13.82.2 Two coats					
	Total Quantity	75	sqm			
7	Other Misc. work as per dsr 2023 on % rate basis 15000		Job			
	Total Gross Amount					

Name & Seal-Sign of Contractor