



मौलाना आजाद राष्ट्रीय प्रौद्योगिकी संस्थान, भोपाल
(शिक्षा मंत्रालय, भारत सरकार के अधीन राष्ट्रीय महत्त्व का संस्थान)
Maulana Azad National Institute of Technology, Bhopal
(An Institution of National Importance under Ministry of Education, Govt. of India)

Date: - 06/08/2026

No. CM/2026/NIQ/4882

NOTICE INVITING QUOTATIONS

The item rate based quotation as per Delhi schedule of Rate CPWD, with up to date amendments are invited for the following work from the empanelled contractors of the Institute. The quotations can be dropped in a box (BOX No. 2) placed at the Civil Maintenance section office till 14-08-2026 at 4:00 PM. The same will be opened on next working day at 11:00 am at Civil Maintenance section office in presence of committee members:-

S.No.	Name of Work	Estimated Cost (in Rs.)	Completion period
1.	Providing and Laying of Cross Drainage Pipe Line for Hostel No. 4, MANIT Bhopal	1,53,873/-	1 month

Salient Feature of Works

1. An agreement will be executed before work order.
2. Rate for each items and amount should be entered along with gross total amount.
3. Other conditions will be same as per Institute norms.
4. Descriptions of Items works are enclosed.
5. Out sourcing / Subletting of work will not be permitted as per rules.
6. Security Deposit of 5% of the bill amount will be retained for a period of 1 year. Any kind of defects occurring during the defect liability period should be repaired by the contractor.

Note: -

1. Authority reserves the right to reject any/all quotation without assigning any reason thereof and can also reduce or enhance the quantity of work.
2. The quotation needs to be submitted on the letter pad of the firm duly sealed and signed on all pages. The envelope containing the quotation should bear/have the details of concerned firm, NIQ No. and name of work.
3. Incomplete quotations will be rejected.

Authority – Approved by competent authority.

[Signature]
06/08/2026 EF
Executive Engineer

Copy to:-

1. Associate Dean (CM)
2. Dean (P&D)
3. Registrar for kind information
4. PA to Director for Kind information of Director.
5. PIC (Website) for uploading on Institute website and intimating uploading confirmation to the undersigned
6. To all empanelled contractors (By e-mail/mobile phone).
7. Display on Notice Board

SCHEDULE OF QUANTITIES

Name of work : Providing and Laying of Cross Drainage Pipe Line for Hostel No. 4, MANIT Bhopal

S. no	Description	Qty	Unit	Rate (Rs. Ps.)- In Figures	Amount (Rs. Ps.)
1	DSR 2023 ITEMS NO. 15.3				
	15.3 Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50metres lead as per direction of Engineer - in- charge.				
	Total Quantity	2.40	cum		
2	DSR 2023 ITEMS NO. 15.2.2				
	15.2 Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
	15.2.2 Nominal concrete 1:4:8 or leaner mix (including equivalent design mix)				
	Total Quantity	2.40	cum		
3	DSR 2023 ITEMS NO. 2.6.1				
	2.6 Earth work in excavation by mechanical means (Hydraulic excavator)/ manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge.				
	2.6.1 All kinds of soil				
	Total Quantity	3.60	cum		
4	DSR 2023 ITEMS NO. 4.1.5				
	4.1 Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
	4.1.5 1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)				
	Total Quantity	1.00	cum		
5	DSR 2023 ITEMS NO. 5.1				
	5.1 Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
	5.1.3 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)				
	Total Quantity	2.70	cum		
	5.1.2 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)				
	Total Quantity	1.80	cum		
6	DSR 2023 ITEMS NO. 5.9.1				
	5.9 Centering and shuttering including strutting, propping etc. and removal of form for				
	5.9.1 Foundations, footings, bases of columns, etc. for mass concrete				
	Total Quantity	16.00	sqm		
7	DSR 2023 ITEMS NO. 5.22.6				
	5.22 Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
	5.22.6 Thermo-Mechanically Treated bars of grade Fe-500D or more.				
	Total Quantity	111.31	kg		

8	DSR 2023 ITEMS NO. 19.36.1				
	19.36 Providing and laying Non Pressure NP-4 class (Heavy duty) R.C.C. pipes including collars/spigot jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete				
	19.36.1 450 mm dia RCC pipes.				
	Total Quantity	20.00	metre		
9	Other Misc. Items on % basis based on DSR 2023 for Rs. 15000/--				
	Total Gross Amount (Rs. Ps.)- In Figures				
	Total Gross Amount (Rs. Ps.)- In words				

Name, Seal & Signature of Contractor